10 MAR 2020 P 0-2 3 - 2 0

RECEIVED

Lot 1

LEGEND:

EXISTING STRUCTURES (GROUND FLOOR)




EXISTING STRUCTURES (UPPER FLOOR)



STRUCTURES TO BE REMOVED

STANDARD DEMOLITION NOTES:

- CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AND DETERMINE THE SCOPE OF WORK REQUIRED. THE CONTRACTOR SHALL EXAMINE THE EXISTING BUILDING AND WORK SHOWN BY ALL CONTRACT DOCUMENTS TO DETERMINE THE SCOPE OF DEMOLITION REQUIRED WHETHER SPECIFICALLY SHOWN OR NOT.
- PROTECT ALL EXISTING STRUCTURE, SYSTEMS, FINISHES AND GENERAL CONSTRUCTION THAT ARE TO REMAIN THROUGHOUT THE COURSE OF THE WORK TO PREVENT DAMAGE OR LOSS, ANY SUCH DAMAGE CAUSED DURING THE COURSE OF THIS WORK WILL BE REPARED AT THE CONTRACTOR'S EXPENSE BEFORE THIS WORK IS CONCLUED.
- CONTRACTOR IS TO VERIFY UTILITY LINE LOCATIONS AND MAINTAIN THOSE THAT SERVE OTHER PARTS OF THE BUILDING THAT ARE NOT AFFECTED BY THE DEMOLITION.
- DEMOLITION CONTRACTOR IS TO ARRANGE FOR SHUT OFF OF EXISTING UTILITIES, CONTRACTOR SHALL ARRANGE ALL TEMPORARY POWER.
- NOISE AND DUST IS NOT TO BE DISRUPTIVE TO THE OCCUPIED AREA OF THE BUILDING, PROVIDE TEMPORARY PARTITIONS AS REQUIRED.
- DEMOLITION IS TO BE DONE IN A CAREFUL AND ORDERLY MANNER SO AS NOT TO DAMAGE FINISHES OR EQUIPMENT TO REMAIN.
- CONTRACTOR IS RESPONSIBLE FOR ALL PATCHING NECESSARY TO EXECUTE THE NEW WORK.
- CONTRACTOR TO OBTAIN & COMPLY WITH ALL BUILDING RULES & REGULATIONS,
- 10. EXISTING ROOF DRAINS TO BE REWORKED AS REQUIRED, COORDINATE LOCATION WITH ARCHITECT & OWNER.
- CONTRACTOR IS RESPONSIBLE FOR DEMOLISHING AND REMOVING ALL MATERIALS FROM PREMISES IN ORDER TO ACCOMPLISH THE SCOPE OF THE NEW WORK.



CLAYTON STREET

DM 07.02 DATE MARK KARWACKI PROJECT DETAILS
64A CLAYTON STREET
EAST FREMANTLE

01 DEMOLITION PLAN

DATEDRAWN 07,02,20		
	DRAWING SCALE 1:200	SHEET SIZE A3
PROJECT MUMBER	DRAWING MUMBER	REVISION
OPDD113	01	Α



ON POINT Drafting & Design Email: dragan@onpoint-drafting.com.au Tel. 0438 761 306

SITE PLAN 1:200

0